

Sheffield Datacentre

Address:

Unit 1, Pioneer Close, Manvers, Rotherham S63 7JZ

Telephone:

0345 119 9911

[BOOK A TOUR](#)

Configuration

Number of Data Halls	2
Total Square Feet	7,282
Total Racks	88
Available Rack Configurations	42U, 600mm x 1000mm ¼ rack, ½ rack, full rack, private cage, dedicated suite

Power

Incoming Supply	1 x 2MW single feed via on-site substation and transformer
UPS Provision	Total of 360kW in an N+1 configuration with 45 minutes of autonomy
Standby Generator Provision	Single 800kW in an N configuration with 13,000 litres of fuel stored on site providing a minimum of 24 hours at full load
Power Delivery to Racks	Single or dual 16Amp or 32Amp single phase

Certifications:



[Learn more](#) about our Sheffield Datacentre or call **0345 119 9911**

Environment

Cooling

Total 720kW cooling capacity in an N+1 configuration provided by blended dry coolers and DX cooling systems

Fire Protection

Double-knock systems, with FM200 fire suppression systems

Floor Void

600mm

On-Net Services

Connectivity

Diverse-routed fibre terminating into separate areas of the building 2 x 1Gb core network links onto Pulsant core network

Carriers

2: BT, Virgin Media

Security

CCTV

24 x 7 CCTV recording with 33 cameras and 90-day retention

Access Control

Electronic card entry, with minimum 12-month retention of access records

Other Systems

Security shutters, Intruder alarm, HD CCTV and IR and Motion detectors, security gates, electronic card entry system, formal access protocols

[Learn more](#) about our Sheffield Datacentre or call **0345 119 9911**



Crown
Commercial
Service
Supplier

